9. Last date for receiving tenders—24th April 1939.

10. Date and time of opening the tenders in public—24th April 1939 at 3 P.M.

11. A period of two weeks will be allowed for final completion of the work with effect from the date of final acceptance of the tender. A penalty of Rs. 10 (Rupees ten) for each day's delay over and above the stipulated period during the first week and Rs. 20 (Rupees twenty) during the second week will be imposed. If there be further delay the department will take charge of the installation at whatever stage it might be and arrange for its completion through any other agency entirely at the risk of the tenderer.

12. It will be obligatory on the part of the tenderer executing the work to attend to any major troubles that might crop up due to bad workmanship, etc., during the first twelve months from the date of handing over the installation to this department without any return for services rendered.

13. *Details of work*:—The quantities given in the annexed statement are not guaranteed and are subject to variation at the time of executing the work.

Details of work:—

	Part "A" (Exterior).	*Quantity.*
1.	Supplying and fixing S.M. rails 30 feet long (50 lbs. section) with tarring complete	5
2.	Supplying and fixing 3-pin D.C.A. complete and tarring the same	5
3.	Supplying and fixing 3-pin S.C.A. complete and tarring the same	2
4.	Supplying and fixing insulators with pins for 800 volts	36
5.	Supplying and stringing H.D. bare copper wire No. 6 B. & S.	168 lbs.
		2,100 Ft.
6.	Supplying and fixing standard telegraph guarding complete	2
7.	Supplying and running cable underground No. 6 A.W.G. 3 conductors L.C.S.A., J.S.V.C. insulated for 600 volts pressure in a trench 3 feet deep and covering it with fine rivers and 3" all round filling it with earth provided with outdoor and indoor junction boxes, pole pipes, etc., complete	190 R.ft.
8.	Supplying and running mains, 3 wires of No. 6 B. & S. insulated wire 2,500 meg ohms grade in 1½" W.I. pipe from cable junction box to meter board	25 ,,
9.	Guy sets complete with anchor rod and 7 stranded guy	6 Sets
10.	Grounding W.I. pipe using 12"×12"×⅛" copper plate	Lumpsum
11.	G.I. or C.I. pipe 3" dia. for running the cable below the railway line ..	180 R.ft.
12.	Excavation below the Railway line and inserting pipe for running the cable ..	160 ,,
	Total ..	

K. SUBBA RAO,
Superintendent.

OFFICE OF THE SUPERINTENDENT, WAY AND WORKS, MYSORE STATE RAILWAY, MYSORE.

Notice dated 15th March 1939.

The undersigned will receive applications up to 31st March 1939, from candidates who are Mysoreans, belonging to Backward Communities and possess good physique. Only those who hold the S.S.L.C. Certificate and also have passed out from the School of Engineering, Bangalore in Mechanical or Electrical Engineering, need apply.

The selected candidate will be on probation for a period of not less than one year, during which he will be given a pay of Rs. 30 per mensem, and be trained for the work of Assistant Signal Inspector. On satisfactory completion of the probationery period, he will be confirmed on Rs. 35 in the grade of Rs. 35—5—2—80.

R. N. MIRZA,
Superintendent.

OFFICE OF THE DEPUTY DIRECTOR OF PUBLIC INSTRUCTION, MYSORE.

Notification No. B1-647-131—36-37, dated 23rd March 1939.

AUCTION SALE.

The public are hereby informed that the date of auction sale of the "Turning Lathe Machine" of the Central Adikarnataka Institute, Mysore, which was fixed for 25th March 1939 is postponed to *5th April* 1939.

K. N. KINI,
Offg. *Deputy Director.*